

BRUHATH BANGALORE MAHANAGARA PALIKE,

DASARAHALLI ZONE

Name OF Work: Augmentation of Water Supply through Borewells, Network of Pipelines and ground water Recharges facilities in areas layouts of Shettyhalli Village. Abbigere Village & Chikkasandra village for Cost of Rs 2.10 Crore.

DRAFT TENDER SCHEDULE (DTS)

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	Geophysical investigation of site for Sinking borewell for supplying drinking water to the habitations either through the hand pump,MWS,P.W.S.S by vertical electrical sounding by adopting venner or Schlumberger's method,including reconnaissance survey of Geological formation. Geophysical investigation of existing ground indecundity its quality & acceptability of the users indicating the location of site,recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe,depth of drilling required to cover full depth of aquifer proposed to be tapped,probable yield and other information required including transportation of instrument and accessories to work site,engaging technical personal and labour required etc.,(Issue rate as on date 02/05/2019 It.13.04)	Nos	18.00	3768.00	Rupees Three Thousand Seven Hundred Sixty Eight Only
2	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) (Issue rate as on date 02/05/2019 It.13.01)				
	0 to 50 m	Rmtr	900.00	347.00	Rupees Three Hundred Forty Seven Only
	50 to 100 m	Rmtr	900.00	442.00	Rupees Four Hundred Forty Two Only
	100 to 150 m	Rmtr	900.00	456.00	Rupees Four Hundred Fifty Six Only
	150 to 200 m	Rmtr	900.00	536.00	Rupees Five Hundred Thirty Six Only
	200 to 250 m	Rmtr	900.00	634.00	Rupees Six Hundred Thirty Four Only
	250 to 300 m	Rmtr	900.00	700.00	Rupees Seven Hundred Only
	300 to 350 m	Rmtr	882.00	825.00	Rupees Eight Hundred Twenty Five Only
3	Providing and fixing unplasticised PVC pipes with working pressure 10 kg/sq.cm with pipe fittings, clips, making good the floor, including cost of all materials, labour charges, HOM and testing complete as per specifications. -do- with 250mm outer dia (Casing Pipe)(KPWD SR 2018-19 Page No:- Item No:- 11.56.7)	Rmt	450.00	2894.00	Rupees Two Thousand Eight Hundred Ninety Four Only
4	Supply of ISI Mark 175mm nominal Bore, Plain end steel casing Pipe-grade of steel Fee 4100 of wakk thickness 504mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel electric or basic oxygen process in fandum length of 5 to 7mtr. Both ends threaded confirming to Is554/1985 one end fixed with socket confirming to IS 270:2001 and other end with screwed pipes. All pipes shall be reasonably free from defectes. The tubes shall be resonably straighth should be with ISI Marking Weighting 25.10 kg/mtr (Inclusive of all taxes and durties) Prices include Collar - medium duty. (Page No.III,It no.84)PRED SR 2012-13.	Rmt	1080.00	1325.00	Rupees One Thousand Three Hundred Twenty Five Only

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
5	Providing 175mm Dia M.S. Collar (P.No XLVII, I.No.17) PRED SR 2012-13	No	180.00	150.00	Rupees One Hundred Fifty Only
6	Providing 175mm dia Borewell Cap & Clamp Set (P.No XLVII, I.No.17) SR 2018-19	Sqm	18.00	1800.00	Rupees One Thousand Eight Hundred Only
7	Submersible Three phase (6 inch/150mm) and other equipments pumps 15 HP/11KW (35 stage) (Pg No. XLI. Sl.no.37) KPWD SR-2018-19	No	18.00	67724.00	Rupees Sixty Seven Thousand Seven Hundred Twenty Four Only
8	Providing and fixing in trenches galvanised/mild steel tube 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipment and testing complete as per specifications. Specification No. KBS 13.2.14/13.6 (page no. XLVII/It no.1) KPWD SR 2018-19. G.I. Pipe 50mm 'B' Class	Rmt	5076.00	439.90	Rupees Four Hundred Thirty Nine And Paise Ninety Only
9	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 to IS 8130-1984 and virgin grade PVC insulation and power coating extruded PVC sheathed suitable for working voltage upto 1100 volts with specified IS 694:1990 and confirming to the attached GTP of group A 3CX6.0 sq.mm (PWD Ele SR 2019-20, P-12/It-2.6.4)	Rmt	10296.00	205.00	Rupees Two Hundred Five Only
10	Providing and fixing in position 50mm Nominal bore non-return Valve verticle type of approved make including cost of all materials, labour HOM of equipment with all lead complete as per Specification (PWD SR 2018-19, P-XLVII SL No-16).	No	18.00	1908.00	Rupees One Thousand Nine Hundred Eight Only
11	Sppllyng and fixing 50mm GI Union. (PWD SR 2016-17, P-XXXIX)	No	18.00	223.70	Rupees Two Hundred Twenty Three And Paise Seventy Only
12	Sppllyng and fixing 50mm GI Elbow. (PWD SR 2016-17, P-XXXIX)	No	18.00	111.80	Rupees One Hundred Eleven And Paise Eighty Only
13	Sppllyng and fixing 50mm GI Nipple. (PWD SR 2016-17, P-XXXIX)	No	18.00	104.30	Rupees One Hundred Four And Paise Thirty Only
14	Sppllyng and fixing 50mm GI Hose collers (PWD SR 2016-17, P-XXXIX)	No	846.00	103.00	Rupees One Hundred Three Only
15	Fabricating ,Supplying and mounting MS Box made out of 16swg suitable for floor mounting , fully weather proof with provision for better dissipation provided with hinged front cover, equipped with tamper proof locking arrangements with suitable size clamps, if necessary cable entry gland and box should be finished with red oxide and two coats of approved colour enameled metal paint etc, complete (Outdoor Panel Box upto 15HP) (PWD SR 2018-19. P-XLVII SL-12)	No	18.00	16430.00	Rupees Sixteen Thousand Four Hundred Thirty Only
16	Supplying and fixing angle iron frame work Fabricated out of MS angle iron and MS flat with bolts nuts washers, etc and painted with two coats of Red oxide and pants (BWSSB SR 2016-17. P-524 I-38(a))	No	18.00	338.00	Rupees Three Hundred Thirty Eight Only
17	Supplying and fixing 20" x 20" x 2.5" polished wood board made of not less than 15mm thick plank on both the sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P.no.24 / I no. 5.6.6 KPWD ELE SR 2019-20	No	18.00	292.00	Rupees Two Hundred Ninety Two Only

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
32	Supplying and fixing porcelain fuse channel with cut out on the existing wooden block and wiring complete 63 amps(PWD Ele SR 2019-20.p- 25.lt-5.7.3)	No	54.00	227.00	Rupees Two Hundred Twenty Seven Only
33	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5	Cum	540.00	475.94	Rupees Four Hundred Seventy Five And Paise Ninety Four Only
34	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (external work) - 50mm nominal OD pipes	Rmt	1060.00	457.92	Rupees Four Hundred Fifty Seven And Paise Ninety Two Only
35	Making connection of G.I.distribution branch with G.I.main of 25mm to 40mm. Nominal bore, including cutting and threading the pipes,providing and fixing Tee, nuts,labour for all item of works,testing and HOM of equipments complete as per specifications.	Rmt	100.00	511.98	Rupees Five Hundred Eleven And Paise Ninety Eight Only
36	Stone dust / Grit 4.75 mm to 0.075 mm	Cum	180.00	1060.00	Rupees One Thousand Sixty Only
37	KSRB 2-4 : Refilling available around earth pipe lines,cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. And lift upto 1.5m. Including cost of all labour complete as per specifications.	Cum	324.00	128.26	Rupees One Hundred Twenty Eight And Paise Twenty Six Only
38	Loading and unloading of stone boulder/stone aggregates/sand/kanker/ moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	Cum	162.00	97.96	Rupees Ninety Seven And Paise Ninety Six Only
39	KSRB 2-4 : Providing and fixing in position brass gate valve with C.I.wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials,labour and HOM of equipments with all leads complete as per specifications.	Each	53.00	1843.34	Rupees One Thousand Eight Hundred Forty Three And Paise Thirty Four Only
40	KSRB13-6.2-1 : Providing and fixing in position brass stop cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3	Each	105.00	149.46	Rupees One Hundred Forty Nine And Paise Forty Six Only
41	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406.)	Cum	180.00	2001.28	Rupees Two Thousand One And Paise Twenty Eight Only
42	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. Clause 502 of MORTH V revision	Sqm	540.00	33.92	Rupees Thirty Three And Paise Ninety Two Only

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
43	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 505 of MORTH V revision - do - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen	Cum	27.00	8545.72	Rupees Eight Thousand Five Hundred Forty Five And Paise Seventy Two Only
44	KSRRB M500-10. Providing and applying tack coat using 80/100 grade bitumen(VG10) in boiler fitted with spray set distributor at the rate of 0.25 kg per sqm on the existing prepared bituminous surface cleaned with mechanical broom. (primed surface) complete as per specifications. Clause 503 of MORTH V revision	Sqm	540.00	10.60	Rupees Ten And Paise Sixty Only
45	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision - do - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen	Cum	21.60	10001.10	Rupees Ten Thousand One And Paise Ten Only
46	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5	Cum	55.30	475.94	Rupees Four Hundred Seventy Five And Paise Ninety Four Only
47	Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	38.48	5408.12	Rupees Five Thousand Four Hundred Eight And Paise Twelve Only
48	Providing and laying in position reinforced cement concrete of Design Mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregates @ 0.47cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reaffirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, columns pillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	90.32	5647.68	Rupees Five Thousand Six Hundred Forty Seven And Paise Sixty Eight Only
49	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	194.40	379.48	Rupees Three Hundred Seventy Nine And Paise Forty Eight Only
50	Providing and fixing RCC precast cover slab of 250 mm thick for Chamber in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including formwork, lift charges, curing and concrete finished surfaces on both sides etc., complete as per drawing and directions of engineer-in-charge. Data rate	Sqm	40.50	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Sl. No	Description of work	Unit	Qty	Amount	
				In Figures (Rs.)	In Words (Rs.)
51	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 Complete with all lead and lift and as per the direction of the Engineer-in-Charge.	Tonne	1.91	92662.02	Rupees Ninety Two Thousand Six Hundred Sixty Two And Paise Two Only
52	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5	Cum	41.54	484.92	Rupees Four Hundred Eighty Four And Paise Ninety Two Only
53	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5.84	5510.16	Rupees Five Thousand Five Hundred Ten And Paise Sixteen Only
54	Providing and constructing granite/trap/basalt size stone masonry in basement with cement mortar 1: 6 stone chisel dressed in courses not less than 15 cms high bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications	Cum	24.08	5921.64	Rupees Five Thousand Nine Hundred Twenty One And Paise Sixty Four Only
55	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cm thick well compacted in foundation and plinth and cills, including cost all materials, labour, HOM of machinery, curing complete as per specifications	Cum	2.72	5855.76	Rupees Five Thousand Eight Hundred Fifty Five And Paise Seventy Six Only
56	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 5.00 N/mm ² conforming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	95.76	1029.24	Rupees One Thousand Twenty Nine And Paise Twenty Four Only
57	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.70cum and fine aggregates @ 0.47cum, with superplasticiser @ 3lts conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete but	Cum	7.77	6528.60	Rupees Six Thousand Five Hundred Twenty Eight And Paise Sixty Only

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
58	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500	Tonne	0.70	94410.36	Rupees Ninety Four Thousand Four Hundred Ten And Paise Thirty Six Only
59	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundation s, footings ,bases of columns for mass concreet including cost of all materials, labour complete as per specifications. (P-16, I-4.28)	Sqm	10.92	278.64	Rupees Two Hundred Seventy Eight And Paise Sixty Four Only
60	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification. Specification No. KBS 4.6.2	Sqm	28.00	475.20	Rupees Four Hundred Seventy Five And Paise Twenty Only
61	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.	Sqm	35.74	1330.56	Rupees One Thousand Three Hundred Thirty And Paise Fifty Six Only
62	Providing and fixing colour glazed tiles of size 300mmx600mm for walls with borders of size 300x100mm, set in Cement Mortar 1:3 and pointed with white cement with matching colour pigment with necessary curing, cleaning including providing and removing scaffolding wherever necessary etc., complete. The work includes cost of all materials, mortar, labour charges for all items of work, hire charges for equipment etc., complete as per specification.	Sqm	30.10	1308.96	Rupees One Thousand Three Hundred Eight And Paise Ninety Six Only
63	Providing 18mm thick cement plaster in single coat with cement mortar 1:3 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	90.12	298.08	Rupees Two Hundred Ninety Eight And Paise Eight Only
64	KSRB15-3 : Providing 15mm thick cement plaster in single coat with cement mortar 1:3 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	72.00	252.72	Rupees Two Hundred Fifty Two And Paise Seventy Two Only
65	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	92.28	110.16	Rupees One Hundred Ten And Paise Sixteen Only
66	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drpos and other foreign matter including preparing the surface even asn sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	72.00	118.80	Rupees One Hundred Eighteen And Paise Eighty Only

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
67	KSRB 7.5 : Providing and fixing pull and push type rolling shutters of approved make out of 18 gauge, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 m	Sqm	12.60	2815.56	Rupees Two Thousand Eight Hundred Fifteen And Paise Fifty Six Only
68	Supplying and installation of 2000 LPH RO drinking water treatment plant comprising of raw water storage tank, anlt scaling dosing system with pump and tank sand filter activated carbonfilter, high pressure pump R.O membranes, R.O pressure tubes, skid house the complete R.O palnte, control panel, chemical cleaning tank, ph dosing system with pump and dosing tank product water storage UV sterilizer, interconnection piping whithin SKID,complete instrumentation with necessary gagues and flow indicator as required in the plante with PH meter etc..(Approved Data rate)	No,s	2.00	650000.00	Rupees Six Lakh(s) Fifty Thousand Only
69	BESCOM deposit Charges and miscellaneous	Each	21.00	13500.00	Rupees Thirteen Thousand Five Hundred Only
70	0302 Polyethylene water storage tank of specified capacity and make	L	10000.00	5.08	Rupees Five And Paise Eight Only



[Signature]
Executive Engineer,
Dasarahalli Division

ಕಂಡಿಕೆ () ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (ಸಾ.ಎಂ.ಇ.) ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಪರವಾಗಿ ಒಳಪಡಿಸಿ ಡಿ.ಐ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಚೀಟರ್ ಪಡ್ಯೋಲ್ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿವೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ: -2೯೫೦-
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಿಗಳ ಸಂಖ್ಯೆ: -2೯೫೦-
[Signature]
ಮುಖ್ಯ ಅಭಿಯಂತರರು (ದೃಢೀಕರಣ)